

HACN HOUSING REHAB SITE DIRECTIONS

Name: <u>Joseph Hogner</u> Telephone: <u>(918)207-7078</u>

Address:


20155 W Quail Dr

Cookson, OK 74427

County: Cherokee

Year Built: 1986

GPS Coordinates: 35.70909, -94.94605 Drive Time: 25 Min



Directions: From Cherokee Nation, Continue to US-62 W 55 sec (0.2 mi) Follow State Hwy 82 to W Cookson Bend Rd in Cookson 16 min (14.1 mi) Turn right onto US-62 W 0.4 m At the traffic circle, take the 2nd exit onto State Hwy 82 13.7 mi Continue on W Cookson Bend Rd. Drive to W Quail Dr 4 min (1.5 mi) Turn right onto W Cookson Bend Rd 1.3 mi Turn left onto S Hickory Dr 0.1 mi Turn right onto W Quail Dr Destination will be on the left 0.1 mi 20155 W Quail Dr Cookson, OK 74427

 Rodney Carman
 (918) 506-9858
 9/4/2024

 Cost Estimator/Inspector
 Date

WorkWrite-Up and Bid Document/By Trade

Joseph Hogner	Contractor Name:		
20155 W Quail Dr Cookson, OK 7-4427	Contractor Signature:		
(310) 201-1010	This document must be si	be signed to be a valid bid.	d.
PROJECT TYPE:	TTYPE: Emergency Repairs	Bid Due Date:	
Trade Work Description / Comments	nents Gen. Spec.	Qty Unit	Item Bid
Carpentry		1	
1 Area: BATHROOM #1	<i>Div.</i> #16.B.2	1Ea	
Door Opening/Widen/Interior/Bathroom/Widen/Install new door/ pre-hung. Work shall include new door, framing, lockset, floor transition, paint and trim.	all new door/ pre-hung. Work shall paint and trim.		
2 Area: BATHROOM #1	Div.#11.2.Z	1 Ea	
Rest room ADA Mirror/ Replace existing medicine cabinet with a Fixed Tilt, 24" in x 36" in. Satin Stainless Steel Tilt Mirror.	abinet with a Fixed Tilt, 24" in x 36"		
Drywall & Finish			
3 Area: BATHROOM #1	Div.#9.D.1	40 SF	CO. C. C. C.
Ceiling Popcorn Texture/Ceiling/ Remove Popcorn Texture	Texture.		
4 Area: BATHROOM #1	Div.#9.D	28 SF	
Drywall/Walls /Repair drywall /Finish completely. Work shall include tape, bed & texture paint to match existing surfaces.	ork shall include tape, bed & texture		
Repair hole behind mirror and above shower surround	nd		

Trade Work Description / Comments	Gen. Spec.	Qty Unit	Item Bid
ryw	<i>Div.</i> #9.F	40 SF	
5 Area: BATHROOM #1	DIV.# 3.1	5	
Texture/celing I/Replace. Replace celing texture, match existing.			
retexture with orange medium peel			
Electrical			
6 Area: BATHROOM #1	<i>Div.</i> # 13.D.	E B	
Light Fixture, Switch & Circuit/ Bathroom. Install new bulb fixture over the vanity, switch, cover plate and circuit.	the vanity, switch,		
7 Area: BATHROOM #1	<i>Div.</i> #13.D. 16	1 Ea	
Light Fixture/Heat-Vent-Light/Install new bathroom light (100 watt), heater (1450 watt), vent fan (70 CFM) and switch. Fan shall be vented out of attic to code.	eater (1450 watt),		
Flooring			
8 Area: BATHROOM #1	Div.#9.L	40 SF	
Flooring/ Install vinyl/waterproof/flooring planks/base trim. Install vinyl planks with 20 mil wear layer, 5.0 mil backing with 25 year residential warranty. Work shall include floor level, seal concrete, moisture resistant glue and top seal.	l planks with 20 mil all include floor		
Paint & Finish			
9 Area: BATHROOM #1	Div.#9.N.3	185 SF	
Paint Interior /Ceilings, Walls, & Trim /Paint Two coats, . Work shall include minor repairs to surfaces. SF=ACTUAL SURFACE AREA OF WALLS & CEILING.	nclude minor ILING.		
Plumbing			
10 Area: BATHROOM #1	Div.# 11.A	1 Ea	
Bathtub/Shower/Demolition. Remove bathtub/shower.			
Print Date: Wednesday, September 4, 2024	20155 W Quail Dr Cookson, OK 7-4427		Page 2 of 3

Trade Work Description / Comments	Gen. Spec.	Qty Unit	Ite	Item Bid
Plumbing				
11 Area: BATHROOM #1	Div.# 16.C.	1 Ea		
Commode/High Rise/Handicap /Replace commode with new high rise/Handicap commode with Seat & two (2) grab bars. include new shutoff, supply line and wax ring. Examine condition of the flange and report if damaged. Consult owner for location of grab bars	dicap and wax ring. ocation of grab			
12 Area: BATHROOM #1	Div.# 16.C.	1Ea	_	
Lavatory Sink & Faucet/ADA/Wall Hung. Install new wall hung lavatory sink supply lines, drain lines, shutoffs, escutcheon plates, insulation for all water and drainlines. Use Orion #52000020 sink, Delta model 520-WFMPU faucet or written approved equal.	supply lines, es. Use Orion al.			
Install lever handle faucet				
13 Area: BATHROOM #1	Div.# 16.C.	1Ea		
Shower/Handicap/Pre-Fab/Install new 32" x 60" x 74" /Pre-fab 3 piece with grab bars, Fold down shower seat, and pressure balanced shower valve with glide bar. Includes all necessary Plumbing.	grab bars, Includes all			
Transfer shower				
All construction shall be in accordance with local codes, manufacturers' recommended installation procedures, good quality workmanship practices, General Specifications and Lead-Based Paint requirements when applicable. Conflicts between requirements will be resolved by	ers' recommended I Specifications and I ements will be resolv		Total:	

compliance with the more stringent requirement.