

Map data ©2025 Google 1 mi

5014 S Muskogee Ave  
Tahlequah, OK 74464

**Continue to US-62 E/S Muskogee Ave**

- ↑ 1. Head east 52 sec (0.1 mi)
- ↶ 2. Turn left toward US-62 E/S Muskogee Ave 404 ft
- ↷ 3. Turn right toward US-62 E/S Muskogee Ave 36 ft
- ↷ 3. Turn right toward US-62 E/S Muskogee Ave 82 ft

**Follow US-62 E to OK-82 BYP/State Hwy 82 N**

- ↶ 4. Turn left onto US-62 E/S Muskogee Ave 9 min (4.0 mi)
- ↷ 5. Turn right onto US-62 E 1.8 mi
- ↷ 5. Turn right onto US-62 E 2.2 mi

**Continue on OK-82 BYP/State Hwy 82 N. Drive to Mc Kie St**

- ↑ 6. Continue straight onto OK-82 BYP/State Hwy 82 N 5 min (2.3 mi)
- ↑ 6. Continue straight onto OK-82 BYP/State Hwy 82 N 1.8 mi

↪ 7. Turn right onto Wheeler St

0.2 mi

↪ 8. Turn right onto Oklahoma Ave

0.1 mi

↩ 9. Turn left onto Mc Kie St

**i** Destination will be on the left

404 ft

509 Mc Kie St

Tahlequah, OK 74464

Phone # : 918-327-9504




Description	Quantity	Per
<b>ESTIMATE: Roof (Housing Authority of the Cherokee Nation)</b>		Claim #11031, Mary Jones
Approved		
<b>ROOFPLAN: Roofplan</b>		

**Chimney**

1 Siding, Lap, Hardboard 7" Exposure - Remove	100.00	SF
2 Siding, Lap, Hardboard 7" Exposure - Replace	100.00 (110.00)	SF
<input type="checkbox"/> Includes 10% waste on material quantity. <input type="checkbox"/> Siding and trim on chimney		
3 Siding - Prime & Paint	100.00	SF
<input type="checkbox"/> Siding and trim on chimney		

**Roof, Roof 3, Roof 4, Roof 2, Roof 5**

**Roof area:** 3,040.79 SF    **Squares:** 30.4 SQ    **Soffit:** 644.92 SF  
**Eaves:** 149.50 LF    **Ridge:** 35.25 LF



**SHINGLES**

4 Shingles, Laminated/Architectural Good - Tear Out	30.41	SQ
5 Shingles, Laminated/Architectural Good - Replace	30.41 (33.45)	SQ
<input type="checkbox"/> Includes 10% waste on material quantity.		
6 Shingles, Starter Row, Continuous - Replace	149.50 (164.45)	LF
<input type="checkbox"/> Includes 10% waste on material quantity.		
7 Ridge Cap Shingles, Fiberglass, Laminated - Replace	35.25 (38.78)	LF
<input type="checkbox"/> Includes 10% waste on material quantity.		

**UNDERLAYMENTS**

8 Felt, 15LB - Replace	30.41	SQ
------------------------	-------	----

**VENTS AND FLASHINGS**

9 Drip Edge (Rake Only) Aluminum, Pre-Finish Color - Tear Out	190.45	LF
10 Drip Edge (Rake Only) Aluminum, Pre-Finish Color - Replace	190.45 (199.98)	LF
<input type="checkbox"/> Includes 5% waste on material quantity.		
11 Drip Edge (Gutter Apron) Aluminum, Pre-Finish Color, 5" - Tear Out	149.50	LF
12 Drip Edge (Gutter Apron) Aluminum, Pre-Finish Color, 5" - Replace	149.50 (156.98)	LF
<input type="checkbox"/> Includes 5% waste on material quantity.		
13 Flashing, Plumbing Vent Aluminum - Tear Out	2	EA
14 Flashing, Plumbing Vent Aluminum - Replace	2	EA
15 Flashing, Vent Pipe - Prime & Paint	2	EA

**DEBRIS REMOVAL**

16 No debris removal is needed for this estimate. The quantity is small enough that it can be discarded with local trash pick up.		
17 Steep Roof Charge, Asphalt Shingle Roof, 7/12-9/12 - Tear Out	4.24	SQ
18 Steep Roof Charge, Asphalt Shingle Roof, 7/12-9/12 - Replace	4.24	SQ
19 Height Allowance, Roof Covering, 3 Story - Tear Out	0.51	SQ
20 Height Allowance, Roof Covering, 3 Story - Replace	0.51	SQ
21 Steep Roof Charge, Asphalt Shingle Roof, 10/12-12/12 - Tear Out	2.22	SQ



**Housing Authority of the Cherokee Nation**  
 PO Box 1007,  
 Tahlequah, Oklahoma 74465-1007  
 918-456-5482 | 1-800-837-2869

Description	Quantity	Per
<b>ESTIMATE: Roof (Housing Authority of the Cherokee Nation)</b>		Claim #11031, Mary Jones
Approved		
22 Steep Roof Charge, Asphalt Shingle Roof, 10/12-12/12 - Replace	2.22	SQ
23 Valley Flashing, Aluminum - Tear Out	29.10	LF
24 Valley Flashing, Aluminum - Replace	29.10 (30.56)	LF
<input checked="" type="checkbox"/> Includes 5% waste on material quantity.		
25 Dumpster 20 Yard	1	EA
26 Fascia, Wood Cedar 1" x 4" - Remove	77.62	LF
27 Fascia, Wood Cedar 1" x 4" - Replace	77.62 (81.51)	LF
<input checked="" type="checkbox"/> Includes 5% waste on material quantity.		

<b>Minimum Charge Adjustments</b>		
28 Minimum Charge, Painter	1	LS

Total: \_\_\_\_\_

Date: \_\_\_\_\_

Contractor

Signature: \_\_\_\_\_