



Housing Authority of the Cherokee Nation
 PO Box 1007,
 Tahlequah, Oklahoma 74465-1007
 918-456-5482 | 1-800-837-2869

Description	Quantity	Per
ESTIMATE: Structure (Housing Authority of the Cherokee Nation)		Claim #11929, Roger Collins
ROOFPLAN: Roofplan		

General Items

1 Dumpster, 10 Yard

1 EA

Roof, Roof 2

Roof area: 1,819.81 SF Squares: 18.2 SQ Soffit: 351.79 SF Eaves: 102.16 LF Ridge: 72.00 LF	
--	--

2 Shingles, Laminated/Architectural Elite - Replace Includes 10% waste on material quantity.	18.21 (20.04)	SQ
3 Drip Edge (Rake + Eave) Galvanized - Replace Includes 5% waste on material quantity.	184.52 (193.75)	LF
4 Flashing, Neoprene Pipe Jack - Replace	4	EA
5 Tear Off all layers and Haul Away, Shingles	18.21	SQ
6 Sheathing, Roof Plywood, 1/2" - Replace Includes 5% waste on material quantity. replace sheathing where needed	128.00 (134.40)	SF
7 Valley Flashing, Aluminum - Replace Includes 5% waste on material quantity.	30.40 (31.92)	LF
8 Shingles, Starter Row, Continuous - Replace Includes 10% waste on material quantity.	102.16 (112.38)	LF
9 Fascia, Cedar, 1"x8" - Replace Includes 5% waste on material quantity. caulk and paint	184.52 (193.75)	LF
10 Vent Pipe Flashing, Furnace, Aluminum, 4" - Replace	2	EA
11 Ridge Cap Shingles, 3-Tab - Replace Includes 10% waste on material quantity.	72.00 (79.20)	LF
12 Roof Vent, Static, Box/Turtle, Aluminum - Replace	4	EA
13 Felt, Single Layer, 30 lb. - Replace	18.21	SQ

Total: \$ _____
 Date: _____
 Contractor Signature: _____