

# Work Write-Up and Bid Document/By Trade

**William Wicks**

Contractor Name:

622 W Olive Stilwell, OK 7-4960

(918) 575-6085

Contractor Signature:

*This document must be signed to be a valid bid.*

**PROJECT TYPE: Rehabilitation**

**Bid Due Date:**

Trade	Work Description / Comments	Gen. Spec.	Qty Unit	Item Bid
<b>Roofing</b>				
1	<i>Area: EXTERIOR</i> Roofing/Architectural/30 Year Warranty. Install architectural shingles/Minimum 30 year warranty/Use Owens Corning "Classic" or written approved equal. <b>Remove &amp; replace all shingles, felt, flashing &amp; drip edge</b>	Div.# 7.A.	28 Sq	<input style="width: 100px; height: 30px;" type="text"/>
<b>Sheetmetal &amp; Gutters</b>				
2	<i>Area: EXTERIOR</i> Roof Jack/Replace/2". Replace plumbing roof jack / 2" pipe. <b>Install new roof jacks</b>	Div.# 5.J	2 Ea	<input style="width: 100px; height: 30px;" type="text"/>
3	<i>Area: EXTERIOR</i> Roof Jack/Replace/4". Replace plumbing roof jack / 4" pipe. <b>Install new roof jack</b>	Div.# 5.J	1 Ea	<input style="width: 100px; height: 30px;" type="text"/>
4	<i>Area: EXTERIOR</i> Vent/Install/Turbine. Install new turbine vent. <b>Install new roof vents</b>	Div.# 5.J	4 Ea	<input style="width: 100px; height: 30px;" type="text"/>

**Site Work**

Trade	Work Description / Comments	Gen. Spec.	Qty Unit	Item Bid
<b>Site Work</b>				
5 Area: EXTERIOR	Cleanup/Final. Final cleanup of entire Project. Remove all trash & debris. Pick all roofing nails with magnet.		1 SF	<input type="text"/>
<p>All construction shall be in accordance with local codes, manufacturers' recommended installation procedures, good quality workmanship practices, General Specifications and Lead-Based Paint requirements when applicable. Conflicts between requirements will be resolved by compliance with the more stringent requirement. Contractor awarded the job will be responsible for conducting safe work practices that comply with OSHA Construction Standards for Asbestos Workers. Asbestos report, where required, will be attached if areas tested are 1% or greater. See attached Asbestos Sampling Report for location and testing of Planned Work Activities.</p>				<p><b>Total:</b> <input type="text"/></p>