



Housing Authority of the Cherokee Nation
 PO Box 1007,
 Tahlequah, Oklahoma 74465-1007
 918-456-5482 | 1-800-837-2869

#14482

Description	Quantity	Per
-------------	----------	-----


ESTIMATE: Roof (Housing Authority of the Cherokee Nation)

Approved

ROOFPLAN: Roofplan

Roof 2, Roof, Roof 3

Roof area: 2,245.44 SF Squares: 22.5 SQ Soffit: 510.40 SF
 Eaves: 153.52 LF Ridge: 76.76 LF



1 Shingles, Composition, Laminated/Architectural, Good - Tear Out	22.46	SQ
2 Shingles, Composition, Laminated/Architectural, Good - Replace <input type="checkbox"/> Includes 10% waste on material quantity.	22.46 (24.70)	SQ
3 Ridge Cap Shingles, 3-Tab - Replace <input type="checkbox"/> Includes 10% waste on material quantity.	76.76 (84.43)	LF
4 Felt, Single Layer, 30 lb. - Replace <input type="checkbox"/> Includes 5% waste on material quantity.	22.46 (23.59)	SQ
5 Drip Edge, Rake, Aluminum, Pre-Finished Color - Tear Out	175.56	LF
6 Drip Edge, Rake, Aluminum, Pre-Finished Color - Replace <input type="checkbox"/> Includes 5% waste on material quantity.	175.56 (184.34)	LF
7 Gutter Apron, Aluminum, Pre-Finished Color, 5" - Tear Out	153.52	LF
8 Gutter Apron, Aluminum, Pre-Finished Color, 5" - Replace <input type="checkbox"/> Includes 5% waste on material quantity.	153.52 (161.19)	LF

SHINGLES

Line 1-8 - \$ _____

9 Shingles, Starter Row, Eave, Continuous - Replace <input type="checkbox"/> This item has been applied to the eaves+rakes of the roof. <input type="checkbox"/> Includes 6% waste on material quantity.	329.08 (348.82)	LF
--	-----------------	----

UNDERLAYMENTS

Line 9 \$ _____

VENTS AND FLASHINGS

10 Roof Vent, Static, Box/Turtle, Aluminum - Tear Out	8	EA
11 Roof Vent, Static, Box/Turtle, Aluminum - Replace	8	EA
12 Flashing, Pipe Jack, Galvanized - Tear Out	3	EA
13 Flashing, Pipe Jack, Galvanized - Replace	3	EA
14 Flashing, Vent Pipe - Prime & Paint	3	EA

DEBRIS REMOVAL

Line 10-14 \$ _____

15 No debris removal is needed for this estimate. The quantity is small enough that it can be discarded with local trash pick up.		
16 Fascia, Cedar, 2"x8" - Remove	329.08	LF
17 Fascia, Cedar, 2"x8" - Replace <input type="checkbox"/> Includes 5% waste on material quantity.	329.08 (345.53)	LF
18 Gutter, K-Style, Aluminum, 5" - Tear Out	32.00	LF
19 Gutter, K-Style, Aluminum, 5" - Replace <input type="checkbox"/> Includes 5% waste on material quantity.	153.52 (161.19)	LF

GUTTER ITEMS

Line 15-19 \$ _____

DOWNSPOUT ITEMS

20 Downspout, Aluminum, 2"x3" - Tear Out	10.00	LF
--	-------	----



Housing Authority of the Cherokee Nation
 PO Box 1007,
 Tahlequah, Oklahoma 74465-1007
 918-456-5482 | 1-800-837-2869

#14482

Description	Quantity	Per
ESTIMATE: Roof (Housing Authority of the Cherokee Nation)		
Approved		
21 Downspout, Aluminum, 2"x3" - Replace	40.00 (42.00)	LF
Includes 5% waste on material quantity.		
22 Fascia, Over 6" - Prime & Paint	329.08	LF
23 Dumpster, 20 Yard	1	EA

Line 20-23 \$ _____

Total : \$ _____

Date : _____

Contractor

Signature: _____